


Electrical Details / Finishes Schedule



EXISTING / PROPOSED ELECTRICAL PLAN; (To be confirmed by Owner) Scale: 1:100

WORKS SCHEDULE - PROVIDE or CHECK FOR COMPLIANCE 1. Provide Smoke Door - NB; Smoke doors may be held open with electro - magnetic hold open connected to FIP for closure 2. Fit Smoke Seals (If not already located) 3. Ensure all rooms have smoke or thermal detectors. Preference for smoke detectors unless room not suitable (spurios alarms) then thermal - connected to FIP - As 1670.1 compliant 4. Fire Extinguisher; 2A 40 B(E) Dry Chemical 5. Fire Extinguisher; 5B (E) CO2

OTE:

All G.P.O.'s are to be mounted at 150mm above floor level unless noted otherwise.

CONTRACTOR'S NOTE;

- 1. Light switch locations to be confirmed on site
- Where installed provide power outlets to dish washer, cook top, spa heating unit, rangehood, wall oven and garage doors. (Remote control motor).
- 3. Supply and installation of light fittings are not included. (batten holders only)
- The location of items on this drawing may vary at Builders discretion due to construction constraints.

ELECTRICAL LAYOUT

SNO-LINE DESIGN SERVICES

ALLAN J. POYNER, P.O. BOX 158, BRIGHT. VIC. 3741 PH: 03-57552011 0.0 PAX: 03-57501151 EMAIL; sno-lin@bigpond.net.au



2.0m 3.0m 4.0m 5.0m 6.0m SCALE; 1:100

BUILDING PRACTIONER; DP - AD 1275

CHECKED		DRAWN	A.J.P.
DATE;	9/5/2012	DESIGNED	
AMENDED: 9/5/2012			

AMENDED; 9/5/2012, 16/5/2012, 17/5/2012, 7/6/2012, 13/6/2012

DRAWING NUMBER; 26D.2012 4 of 6